

## COCHIN PORT TRUST

[www.tenderwizard.com/COPT](http://www.tenderwizard.com/COPT)



Tender No: T6/T-1908/2019-C Date: 16/12/2019 (PRICE BID)

**Name of Wok: "PROVIDING AND LAYING CC PAVER BLOCKS AT DRISHTY JUNCTION"**

### SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Providing, laying, spreading and compacting graded stone aggregate (size range 53 mm to 0.075 mm ) to wet mix macadam (WMM) specification including premixing the material with water at OMC in for all leads & lifts, laying in uniform layers with mechanical paverfinisher in sub- base / base course on well prepared surface and compacting with vibratory roller of 8 to10 tonne capacity to achieve the desired density, including cost of all labour, materials, equipments etc. complete as per detailed specifications and directions of Engineer-in-Charge.	90.00	One cubic metre	3589.77	<b>Rupees Three Thousand Five Hundred Eighty Nine and Seventy Seven Paise Only</b>	323079.30	<b>Rupees Three Lakh Twenty Three Thousand Seventy Nine and Thirty Paise Only</b>
2	Providing and laying factory made 100mm thick Cement Concrete paver blocks of M40 grade, thickness & size/ shape, made by table vibratory method , to attain superior smooth finish using PU or equivalent moulds, laid in required colour & pattern over 50mm thick compacted bed of 6mm coarse aggregate, compacting and proper embedding / laying of inter locking paver blocks into the 6mm coarse aggregate bedding layer through vibratory compaction by using plate vibrator, filling the joints with crusher sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in drive ways or traffic parking including cost of all labour, materials, equipments etc. complete as per manufacturer's specifications/ detailed specifications & direction of Engineer -in-Charge	470.00	One square metre	1030.00	<b>Rupees One Thousand Thirty Only</b>	484100.00	<b>Rupees Four Lakh Eighty Four Thousand One Hundred Only</b>

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
3	Transporting surplus materials and debris using mini tipper lorry (3 m <sup>3</sup> ), dumping and levelling within a lead of 6Km including all labour and consumables etc. as per the direction of the Engineer-in-Charge.	1.00	One day of 8 Hrs	4326.00	<b>Rupees Four Thousand Three Hundred Twenty Six Only</b>	4326.00	<b>Rupees Four Thousand Three Hundred Twenty Six Only</b>
	<b>Total</b>					<b>811505.30</b>	<b>Rupees Eight Lakh Eleven Thousand Five Hundred Five and Thirty Paise Only</b>
	<b>Percentage quoted above/ below the departmental amount shown in the above schedule</b> <b>Note : 1.The tenderer shall quote either plus or minus in sign (eg: +5 or -5) and in figures</b> <b>2. Only two decimal digits shall be accepted</b>						
<b>" This is an Electronic Submission No Need of Signature"</b>							