

COCHIN PORT TRUSTwww.tenderwizard.com/COPT

Tender No: T6/T-1916/2020 -C Date: 29.02.2020- (PRICE BID)

Name of Wok: "RENOVATION OF GROUND FLOOR OF CFS BUILDING"**SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT**

Please Enter the Contractor Name

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
T6/T-1916/2020 -C							
1	Dismantling wooden boardings in lining of walls and partitions, excluding supporting members but including stacking within 50 metres lead : Thickness above 25 mm up to 40 mm as per detailed specifications and directions of Engineer-in-Charge.	50.00	m ²	90.44	Rupees Ninety and Forty Four Paise Only	4522.00	Rupees Four Thousand Five Hundred Twenty Two Only
2	Taking out doors, windows and clerestory windows (steel or wood) shutter including chowkhats, architrave, holdfasts etc. complete and stacking within 50 metres lead Area 3 sq. metres and below as per the directions of Engineer-in-Charge.	29.00	each	144.81	Rupees One Hundred Forty Four and Eighty One Paise Only	4199.49	Rupees Four Thousand One Hundred Ninety Nine and Forty Nine Paise Only
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar as per detailed specifications and directions of Engineer-in-Charge.	150.00	m ³	1997.65	Rupees One Thousand Nine Hundred Ninety Seven and Sixty Five Paise Only	299647.50	Rupees Two Lakh Ninety Nine Thousand Six Hundred Forty Seven and Fifty Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
4	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1 kilometre, stacking serviceable and unserviceable material separately including cutting reinforcement bars as per detailed specifications and directions of Engineer-in-Charge.	18.00	m ³	2894.76	Rupees Two Thousand Eight Hundred Ninety Four and Seventy Six Paise Only	52105.68	Rupees Fifty Two Thousand One Hundred Five and Sixty Eight Paise Only
5	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix). as per detailed specifications and directions of Engineer-in-Charge.	90.00	m ³	2361.26	Rupees Two Thousand Three Hundred Sixty One and Twenty Six Paise Only	212513.40	Rupees Two Lakh Twelve Thousand Five Hundred Thirteen and Forty Paise Only
6	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.as per detailed specifications and directions of Engineer-in-Charge.	110.00	m ³	342.89	Rupees Three Hundred Forty Two and Eighty Nine Paise Only	37717.90	Rupees Thirty Seven Thousand Seven Hundred Seventeen and Ninety Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
7	Rebarring for fixing reinforcement work of additional plinth beams using 16mm/ 20mm FE 500D or more grade reinforcement as per detailed specifications and directions of Engineer-in-Charge.	40.00	each	268.00	Rupees Two Hundred Sixty Eight Only	10720.00	Rupees Ten Thousand Seven Hundred Twenty Only
8	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns. as per detailed specifications, drawing and directions of Engineer-in-Charge.	18.00	m ²	387.12	Rupees Three Hundred Eighty Seven and Twelve Paise Only	6968.16	Rupees Six Thousand Nine Hundred Sixty Eight and Sixteen Paise Only
9	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) as per detailed specifications, drawings and directions of Engineer-in-Charge.	32.00	m ³	7868.30	Rupees Seven Thousand Eight Hundred Sixty Eight and Thirty Paise Only	251785.60	Rupees Two Lakh Fifty One Thousand Seven Hundred Eighty Five and Sixty Paise Only
10	Centering and shuttering including strutting, propping etc. and removal of form for : Lintels, beams, plinth beams, girders, brusses and cantilevers as per detailed specifications, drawings and directions of Engineer-in-Charge.	440.00	m ²	750.26	Rupees Seven Hundred Fifty and Twenty Six Paise Only	330114.40	Rupees Three Lakh Thirty Thousand One Hundred Fourteen and Forty Paise Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
11	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III): 3 graded stone aggregate 20 mm nominal size). as per detailed specifications, drawings and directions of Engineer-in-Charge.	90.00	m ³	10489.41	Rupees Ten Thousand Four Hundred Eighty Nine and Forty One Paise Only	944046.90	Rupees Nine Lakh Forty Four Thousand Forty Six and Ninety Paise Only
12	Reinforced cement concrete work in beams, suspended floors, roofs having slope up to 15° landings, balconies, shelves, chajjas, lintels, bands, plain window sills, staircases and spiral stair cases above plinth level up to floor five level, excluding the cost of centering, shuttering, finishing and reinforcement, with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size as per detailed specifications, drawings and directions of Engineer-in-Charge.	11.50	m ³	13269.39	Rupees Thirteen Thousand Two Hundred Sixty Nine and Thirty Nine Paise Only	152597.99	Rupees One Lakh Fifty Two Thousand Five Hundred Ninety Seven and Ninety Nine Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
13	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Thermo-Mechanically Treated bars of grade Fe-500D or more as per detailed specifications, drawings and directions of Engineer-in-Charge.	20500.00	kg	113.48	Rupees One Hundred Thirteen and Forty Eight Paise Only	2326340.00	Rupees Twenty Three Lakh Twenty Six Thousand Three Hundred Forty Only
14	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m as per detailed specifications and directions of Engineer-in-Charge.	60.00	m ³	298.51	Rupees Two Hundred Ninety Eight and Fifty One Paise Only	17910.60	Rupees Seventeen Thousand Nine Hundred Ten and Sixty Paise Only
15	Providing & filling with 6mm metal mixed with quarry dust inside basement including consolidation as per the directions of Engineer-in-Charge.	90.00	m ³	2882.00	Rupees Two Thousand Eight Hundred Eighty Two Only	259380.00	Rupees Two Lakh Fifty Nine Thousand Three Hundred Eighty Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
16	Providing and fixing up to floor five level precast cement concrete solid block, including hoisting and setting in position with cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering, shuttering complete : 1:1½:3 (1 Cement: 1½ coarse sand(zone-III) : 3 graded stone aggregate 20 mm nominal size) as per detailed specifications, drawings and directions of Engineer-in-Charge.	120.00	m ³	19354.16	Rupees Nineteen Thousand Three Hundred Fifty Four and Sixteen Paise Only	2322499.20	Rupees Twenty Three Lakh Twenty Two Thousand Four Hundred Ninety Nine and Twenty Paise Only
17	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead as per detailed specifications and directions of Engineer-in-Charge.	100.00	m ²	53.00	Rupees Fifty Three Only	5300.00	Rupees Five Thousand Three Hundred Only
18	12 mm cement plaster: 1:4 (1 cement : 4 fine sand). as per detailed specifications and directions of Engineer-in-Charge.	1900.00	m ²	362.66	Rupees Three Hundred Sixty Two and Sixty Six Paise Only	689054.00	Rupees Six Lakh Eighty Nine Thousand Fifty Four Only
19	6 mm cement plaster of mix : 1:3 (1 cement : 3 fine sand) as per detailed specifications and directions of Engineer-in-Charge.	150.00	m ²	308.98	Rupees Three Hundred Eight and Ninety Eight Paise Only	46347.00	Rupees Forty Six Thousand Three Hundred Forty Seven Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
20	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS : 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm. as per detailed specifications and directions of Engineer-in-Charge.	360.00	m ²	2039.31	Rupees Two Thousand Thirty Nine and Thirty One Paise Only	734151.60	Rupees Seven Lakh Thirty Four Thousand One Hundred Fifty One and Sixty Paise Only
21	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in colours White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick cement mortar 1:4 (1 Cement: 4 Coarse sand), including grouting the joints with white cement and matching pigments etc., complete as per detailed specifications and directions of Engineer-in-Charge.	30.00	m ²	1479.18	Rupees One Thousand Four Hundred Seventy Nine and Eighteen Paise Only	44375.40	Rupees Forty Four Thousand Three Hundred Seventy Five and Forty Paise Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
22	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete as per detailed specifications and directions of Engineer-in-Charge.	120.00	m ²	1400.22	Rupees One Thousand Four Hundred and Twenty Two Paise Only	168026.40	Rupees One Lakh Sixty Eight Thousand Twenty Six and Forty Paise Only
23	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface : Water thinnable cement primer complete as per detailed specifications and directions of Engineer-in-Charge.	2200.00	m ²	81.54	Rupees Eighty One and Fifty Four Paise Only	179388.00	Rupees One Lakh Seventy Nine Thousand Three Hundred Eighty Eight Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
24	Wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile Organic Compound) content less than 50 grams/ litre of approved brand and manufacture, including applying additional coats wherever required to achieve even shade and colour Two coats complete as per detailed specifications and directions of Engineer-in-Charge.	1500.00	m ²	154.79	Rupees One Hundred Fifty Four and Seventy Nine Paise Only	232185.00	Rupees Two Lakh Thirty Two Thousand One Hundred Eighty Five Only
25	Finishing walls with Acrylic Smooth exterior paint of required shade : Old work (Two or more coat applied @ 1.67 ltr/ 10 sqm) on existing cement paint surface sqm. Two coats complete as per detailed specifications and directions of Engineer-in-Charge.	950.00	m ²	145.15	Rupees One Hundred Forty Five and Fifteen Paise Only	137892.50	Rupees One Lakh Thirty Seven Thousand Eight Hundred Ninety Two and Fifty Paise Only
26	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works complete as per detailed specifications and directions of Engineer-in-Charge.	85.00	m ²	68.90	Rupees Sixty Eight and Ninety Paise Only	5856.50	Rupees Five Thousand Eight Hundred Fifty Six and Fifty Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
27	Providing wood work in frames of doors, windows, clerestory windows and other frames, wrought framed and fixed in position with hold fast lugs or with dash fasteners of required dia & length (hold fast lugs or dash fastener shall be paid for separately). Kiln seasoned and chemically treated hollock wood complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	6.00	m ³	97506.23	Rupees Ninety Seven Thousand Five Hundred Six and Twenty Three Paise Only	585037.38	Rupees Five Lakh Eighty Five Thousand Thirty Seven and Thirty Eight Paise Only
28	Providing and fixing panelling or panelling and glazing in panelled or panelled and glazed shutters for doors, windows and clerestory windows (Area of opening for panel inserts excluding portion inside grooves or rebates to be measured). Panelling for panelled or panelled and glazed shutters 25 mm to 40 mm thick : Kiln seasoned and chemically treated hollock wood complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	6.00	m ²	2649.65	Rupees Two Thousand Six Hundred Forty Nine and Sixty Five Paise Only	15897.90	Rupees Fifteen Thousand Eight Hundred Ninety Seven and Ninety Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
29	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, including ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Kiln seasoned and chemically treated hollock wood 35 mm thick complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	16.00	m ²	4011.00	Rupees Four Thousand Eleven Only	64176.00	Rupees Sixty Four Thousand One Hundred Seventy Six Only
30	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	300.00	kg	178.03	Rupees One Hundred Seventy Eight and Three Paise Only	53409.00	Rupees Fifty Three Thousand Four Hundred Nine Only
31	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade : Two or more coats on new work complete as per detailed specifications and directions of Engineer-in-Charge.	150.00	m ²	165.19	Rupees One Hundred Sixty Five and Nineteen Paise Only	24778.50	Rupees Twenty Four Thousand Seven Hundred Seventy Eight and Fifty Paise Only

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
32	Providing and fixing Fiber Glass Reinforced plastic (FRP) Door Frames of cross-section 90 mm x 45 mm having single rebate of 32 mm x 15 mm to receive shutter of 30 mm thickness .The laminate shall be moulded with fire resistant grade unsaturated polyester resin and chopped mat . Door frame laminate shall be 2 mm thick and shall be filled with suitable wooden block in all the three legs. The frame shall be covered with fiber glass from all sides. M.S. stay shall be provided at the bottom to steady the frame complete as per detailed specifications and directions of Engineer-in-Charge.	35.00	m	923.94	Rupees Nine Hundred Twenty Three and Ninety Four Paise Only	32337.90	Rupees Thirty Two Thousand Three Hundred Thirty Seven and Ninety Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
33	Supplying and fixing rolling shutters of approved make, made of required size M.S. laths, interlocked together through their entire length and jointed together at the end by end locks, mounted on specially designed pipe shaft with brackets, side guides and arrangements for inside and outside locking with push and pull operation complete, including the cost of providing and fixing necessary 27.5 cm long wire springs manufactured from high tensile steel wire of adequate strength conforming to IS: 4454 - part 1 and M.S. top cover of required thickness for rolling shutters. 80x1.25 mm M.S. laths with 1.25 mm thick top cover complete as per detailed specifications and directions of Engineer-in-Charge.	11.00	m ²	4001.15	Rupees Four Thousand One and Fifteen Paise Only	44012.65	Rupees Forty Four Thousand Twelve and Sixty Five Paise Only
34	Providing and fixing ball bearing for rolling shutters complete as per detailed specifications and directions of Engineer-in-Charge.	3.00	each	570.59	Rupees Five Hundred Seventy and Fifty Nine Paise Only	1711.77	Rupees One Thousand Seven Hundred Eleven and Seventy Seven Paise Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
35	Providing and fixing to existing door frames. 30 mm thick Glass Fibre Reinforced Plastic (FRP) panelled door shutter of required colour and approved brand and manufacture, made with fire - retardant grade unsaturated polyester resin, moulded to 3 mm thick FRP laminate for forming hollow rails and styles, with wooden frame and suitable blocks of seasoned wood inside at required places for fixing of fittings, cast monolithically with 5 mm thick FRP laminate for panels conforming to IS: 14856, including fixing to frames complete as per detailed specifications and directions of Engineer-in-Charge.	12.00	m ²	4709.14	Rupees Four Thousand Seven Hundred Nine and Fourteen Paise Only	56509.68	Rupees Fifty Six Thousand Five Hundred Nine and Sixty Eight Paise Only
36	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make. For fixed portion Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	120.00	kg	620.13	Rupees Six Hundred Twenty and Thirteen Paise Only	74415.60	Rupees Seventy Four Thousand Four Hundred Fifteen and Sixty Paise Only

SL.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
37	<p>Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass / stainless steel screws, all. (Glazing, paneling and dash fasteners to be paid for separately) :For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately) Powder coated aluminium (minimum thickness of powder coating 50 micron) complete as per detailed specifications.</p>	170.00	kg	742.51	Rupees Seven Hundred Forty Two and Fifty One Paise Only	126226.70	Rupees One Lakh Twenty Six Thousand Two Hundred Twenty Six and Seventy Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
38	Providing and fixing 12 mm thick prelaminated particle board flat pressed three layer or graded wood particle board conforming to IS: 12823 Grade I Type II, in panelling fixed in aluminum doors, windows shutters and partition frames with C.P. brass / stainless steel screws etc. complete as per architectural drawings and directions of Engineer-in-charge. Pre-laminated particle board with decorative lamination on both sides complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	14.09	m ²	1422.78	Rupees One Thousand Four Hundred Twenty Two and Seventy Eight Paise Only	20046.97	Rupees Twenty Thousand Forty Six and Ninety Seven Paise Only
39	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of Engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item): With float glass panes of 4.0 mm thickness complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	20.00	m ²	1358.50	Rupees One Thousand Three Hundred Fifty Eight and Fifty Paise Only	27170.00	Rupees Twenty Seven Thousand One Hundred Seventy Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
40	Providing and fixing double action hydraulic floor spring of approved brand and manufacture conforming to IS : 6315, having brand logo embossed on the body / plate with double spring mechanism and door weight upto 125 kg, for doors,including cost of cutting floors,embedding in floors as required and making good the same matching to the existing floor finishing and cover plates with brass pivot and single piece M.S. sheet outer box with slide plate etc. complete as per the direction of Engineer-in-charge. With stainless steel cover plate minimum 1.25 mm thickness complete as per detailed specifications, drawings and directions of Engineer-in-Charge.	10.00	each	3278.68	Rupees Three Thousand Two Hundred Seventy Eight and Sixty Eight Paise Only	32786.80	Rupees Thirty Two Thousand Seven Hundred Eighty Six and Eighty Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
41	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid complete as per detailed specifications and directions of Engineer-in-Charge.	4.00	each	7149.84	Rupees Seven Thousand One Hundred Forty Nine and Eighty Four Paise Only	28599.36	Rupees Twenty Eight Thousand Five Hundred Ninety Nine and Thirty Six Paise Only

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
42	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern complete as per detailed specifications and directions of Engineer-in-Charge.	6.00	each	6771.08	Rupees Six Thousand Seven Hundred Seventy One and Eight Paise Only	40626.48	Rupees Forty Thousand Six Hundred Twenty Six and Forty Eight Paise Only

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
43	White Vitreous China Flat back wash basin size 450x300 mm with single 15 mm C.P. brass pillar tap Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require White Vitreous China Wash basin size 630x450 mm with 15 mm C.P. brass pillar taps complete as per detailed specifications and directions of Engineer-in-Charge.	3.00	each	4196.31	Rupees Four Thousand One Hundred Ninety Six and Thirty One Paise Only	12588.93	Rupees Twelve Thousand Five Hundred Eighty Eight and Ninety Three Paise Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
44	Providing and fixing stone slab with table rubbed, edges rounded and polished, of size 75x50 cm deep and 1.8 cm thick, fixed in urinal partitions by cutting a chase of appropriate width with chase cutter and embedding the stone in the chase with epoxy grout or with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 6 mm nominal size) as per direction of Engineer-in-charge and finished smooth. Granite Stone of approved shade complete as per detailed specifications and directions of Engineer-in-Charge.	2.00	m ²	467.65	Rupees Four Hundred Sixty Seven and Sixty Five Paise Only	935.30	Rupees Nine Hundred Thirty Five and Thirty Paise Only
45	Supplying and fixing PVC floor traps 110mm dia. with 50mm deep seal and 63/75mm outlet, complete as per detailed specifications and directions of Engineer-in-Charge.	9.00	each	200.00	Rupees Two Hundred Only	1800.00	Rupees One Thousand Eight Hundred Only
46	Supplying and laying/ fixing 63mm dia. PVC pipe(class 2) buried/ above ground for drainage disposal, complete as per detailed specifications and directions of Engineer-in-Charge.	30.00	each	118.70	Rupees One Hundred Eighteen and Seventy Paise Only	3561.00	Rupees Three Thousand Five Hundred Sixty One Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
47	Laying and jointing PVC pipe (class 5) with ISI mark on walls including all specials for water supply line. 40 mm dia., complete as per detailed specifications and directions of Engineer-in-Charge.	75.00	m	85.30	Rupees Eighty Five and Thirty Paise Only	6397.50	Rupees Six Thousand Three Hundred Ninety Seven and Fifty Paise Only
48	Laying and jointing PVC pipe (class 5) with ISI mark on walls including all specials for water supply line. 25 mm dia., complete as per detailed specifications and directions of Engineer-in-Charge.	40.00	m	53.30	Rupees Fifty Three and Thirty Paise Only	2132.00	Rupees Two Thousand One Hundred Thirty Two Only
49	Laying and jointing PVC pipe (class 5) with ISI mark on walls including all specials for water supply line. 20 mm dia., complete as per detailed specifications and directions of Engineer-in-Charge.	20.00	m	47.70	Rupees Forty Seven and Seventy Paise Only	954.00	Rupees Nine Hundred Fifty Four Only
50	Providing and fixing 15mm dia. or nearest available size Chromium plated brass tap (Heavy Type) of weight not less than 400g, complete as per detailed specifications and directions of Engineer-in-Charge.	8.00	m	375.50	Rupees Three Hundred Seventy Five and Fifty Paise Only	3004.00	Rupees Three Thousand Four Only
51	Providing fixing of mirror of superior glass rectangular shape 453x357mm, complete as per directions of Engineer-in-Charge.	5.00	each	1053.71	Rupees One Thousand Fifty Three and Seventy One Paise Only	5268.55	Rupees Five Thousand Two Hundred Sixty Eight and Fifty Five Paise Only

SL.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
52	Providing and fixing PTMT towel rail complete with bracket fixed to wooden cleats with CP brass screws 600 mm long, complete as per directions of Engineer-in-Charge.	2.00	each	783.88	Rupees Seven Hundred Eighty Three and Eighty Eight Paise Only	1567.76	Rupees One Thousand Five Hundred Sixty Seven and Seventy Six Paise Only
53	Applying priming coat with ready mixed red oxide zinc chromate primer of approved brand and manufacture on steel galvanised iron/ steel works, complete as per directions of Engineer-in-Charge.	16.00	m ²	68.90	Rupees Sixty Eight and Ninety Paise Only	1102.40	Rupees One Thousand One Hundred Two and Forty Paise Only
54	Fixing brass hard drawn hooks and eyes 100 mm 10 Nos, complete as per directions of Engineer-in-Charge.	56.00	10 Nos.	468.87	Rupees Four Hundred Sixty Eight and Eighty Seven Paise Only	26256.72	Rupees Twenty Six Thousand Two Hundred Fifty Six and Seventy Two Paise Only
55	Providing and fixing chromium plated brass butt hinges with necessary chromium plated brass screws etc. complete. 125x70x4 mm (ordinary type), complete as per directions of Engineer-in-Charge.	12.00	each	231.17	Rupees Two Hundred Thirty One and Seventeen Paise Only	2774.04	Rupees Two Thousand Seven Hundred Seventy Four and Four Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
56	Providing and fixing chromium plated brass butt hinges with necessary chromium plated brass screws etc. complete 75x40x2.5 mm (ordinary type), complete as per directions of Engineer-in-Charge.	56.00	each	132.30	Rupees One Hundred Thirty Two and Thirty Paise Only	7408.80	Rupees Seven Thousand Four Hundred Eight and Eighty Paise Only
57	Providing and fixing 85x42 mm chromium plated brass pull bolt lock with necessary chromium plated brass screws, nuts, bolts and washers etc. complete as per directions of Engineer-in-Charge.	3.00	each	333.24	Rupees Three Hundred Thirty Three and Twenty Four Paise Only	999.72	Rupees Nine Hundred Ninety Nine and Seventy Two Paise Only
58	Providing and fixing 85x42 mm chromium plated brass pull bolt lock with necessary chromium plated brass screws, nuts, bolts and washers etc. complete as per directions of Engineer-in-Charge.	315.00	m ³	188.70	Rupees One Hundred Eighty Eight and Seventy Paise Only	59440.50	Rupees Fifty Nine Thousand Four Hundred Forty and Fifty Paise Only
	Total					10839579.13	Rupees One Crore Eight Lakh Thirty Nine Thousand Five Hundred Seventy Nine and Thirteen Paise Only

SL.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
BIDDER'S QUOTING AREA							
	Description of work	Departmental Estimated Cost (Rs)	Percentage Quoted		Above/Below	Bidders Quoted Amount (Rs.)	Bidders Quoted Amount (Rs.) in Words
			* In Figures	# In Words			
	Percentage quoted above/ below the departmental amount shown in the above schedule.	10839579.13					
	<p>* The tenderer shall quote either plus or minus sign (eg: +5 or -5) in figures only and minimum two decimal digits shall only be accepted.</p> <p># Contents in cells under column " In Words" shall be entered by the bidder.</p>						

" This is an Electronic Submission. No Need of Signature"