

ANNEXURE - I

Schedule Of Works for "Shifting and refitting of AC units in the buildings at Cochin Port Trust"

Sl. No.	Description of Work	QTY	Unit	Rate (Rs.)	Amount (Rs.)
1	Dismantling 1.5T split type AC units (Indoor & outdoor items) and re-fixing the same in other buildings of Cochin Port Trust and commissioning the same .	12	Nos		
2	Supply, Installation, Testing & Commissioning of Copper tube	42	M		
3	Gas charging for AC's	12	LS		
4	Supply, Installation, Testing & Commissioning of 3C Copper wire for giving supply to indoor units	36	M		
5	Dismantling the 1.5T AC units Both (Indoor& outdoor items) and handing over to Cochin Port Trust	5	Nos		
6	Supply and fixing the Power coated MS stand for out door units	8	Nos		
	Total quoted amount excluding GST				
	GST				
	Total quoted amount including GST				

SIGNATURE & SEAL OF THE BIDDER