

COCHIN PORT TRUSTwww.tenderwizard.com/CPT

Tender No: T6/T-1956/2021-C Date: 27.12.2021-(PRICE BID)

Name of Wok:"REPAIRING AND PAINTING THE TWO NOS 900 KL PRESSED STEEL OH TANKS AT LEASING AREA AND ERNAKULAM WHARF"

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name							
Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Painting the External Surface of Steel tank & structural support with 1 coat (75 Micron) of Berger Protector CTE MAST Black/ ASIAN RUST O SEAL/ Nerolac Mastic or its approved equivalent paint and 2 coat (75 Micron each) of Berger Epilux 555 Coaltar Black Coating/ ASIAN Coaltar Black Coating/ Nerolac Coaltar or its approved equivalent paint including Scuffholding and labour charges for thorough cleaning using wire brush, emery paper, chipping hammer and buffing wheel to remove the loose rust from the surface including cost of all labour, materials, tools etc. complete. as per detailed specifications and direction of the Engineer in-charge	8528.00	One square metre	383.50	Rupees Three Hundred Eighty Three and Fifty Paise Only	3270488.00	Rupees Thirty Two Lakh Seventy Thousand Four Hundred Eighty Eight Only

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
2	Painting the internal Surface of steel tank with Food Grade High Build Tank lining paint (Berger Epilux 78 HBTL/ ASIAN APCODUR 699/ NEROLAN FOOD GRADE HIGH BUILD TANK LINING) or approved equivalent paints 3 coats (75 Micron each) including Scuffholding and labour charges for Thorough cleaning using wire brush, emery paper, chipping hammer and buffing wheel to remove the loose rust from the surface including cost of all labour, materials, tools etc. complete. as per detailed specifications and direction of the engineer-in-charge	2304.16	One square metre	490.00	Rupees Four Hundred Ninety Only	1129038.40	Rupees Eleven Lakh Twenty Nine Thousand Thirty Eight and Forty Paise Only
3	Structural steel work riveted, bolted or welded in built up sections, and framed work for repairing/ replacing the damaged steel members of tank, stoppage of leak etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete including cost of all materials, tools, equipments etc. complete as per detailed specifications and direction of Engineer-in-charge.	1000.00	One Kilogram	138.28	Rupees One Hundred Thirty Eight and Twenty Eight Paise Only	138280.00	Rupees One Lakh Thirty Eight Thousand Two Hundred Eighty Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
	Total					4537806.40	Rupees Forty Five Lakh Thirty Seven Thousand Eight Hundred Six and Forty Paise Only
BIDDER'S QUOTING AREA							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail 5.Wrongful entry of quotes shall entail disqualifications besides other actions as the Employee deem fit.				4537806.40			
" This is a Electronic Submission No Need of Signature"							