

COCHIN PORT TRUSTwww.tenderwizard.com/COPT

Quotation No:T1/Q-02/2022-C Date:02/02/2022

**Name of Wok: "PROVIDING BARBED WIRE FENCING BY THE SIDE OF NH966B NEAR KANNANGATTU BRIDGE."****SCHEDULE- A- SCHEDULE OF QUANTITIES OF WORK****Please Enter the Contractor Name**

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as per detailed specifications and as directed by the Engineer-in-charge. All kinds of soil	12.50	One Cubic Metre	247.14	Rupees Two Hundred Forty Seven and Fourteen Paise Only	3089.25	Rupees Three Thousand Eighty Nine and Twenty Five Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
2	R.C.C. Standards post/ struts/rails/ pales of mix 1:1.5:3 (1 cement : 1.5 coarsesand : 3 graded stone aggregate 12.5 mm nominal size) with wooden plugs or 6mm bar nibs wherever required as per direction of Engineer-incharge (cost of earth works in excavation, concrete works in foundation to be paid separately) including reinforcement, shuttering, plastering etc. complete as per detailed specificatons and directions of the Engineer-in-charge	5.00	One Cubic metre	36360.23	Rupees Thirty Six Thousand Three Hundred Sixty and Twenty Three Paise Only	181801.15	Rupees One Lakh Eighty One Thousand Eight Hundred One and Fifteen Paise Only
3	Providing and laying in position cement concrete of specified grade sexcluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) : 6 graded stone aggregate 20 mm nominal size) icluding cost of all labour, materials, tools etc. complete as per detailed specifications and directions of Engineer-in-charge.	12.00	One Cubic Metre	8506.37	Rupees Eight Thousand Five Hundred Six and Thirty Seven Paise Only	102076.44	Rupees One Lakh Two Thousand Seventy Six and Forty Four Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
4	Fencing with R.C.C. post placed at required distance, embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post one side only, provided with horizontal lines and two diagonals of barbed wire weighing 9.38 kg per 100 metres (minimum), between the two posts fitted and fixed with G.I. staples on wooden plugs or G.I. binding wire tied to 6 mm bar nibs fixed while casting the post (cost of R.C.C. posts, struts, earth work and concrete to be paid for separately) :- Payment to be made per metre cost of total length of barbed wire used. With G.I. barbed wire including cost of all labour, materials etc. complete as per detailed specifications and directions of the Engineer-in-charge	1500.00	One metre	16.31	Rupees Sixteen and Thirty One Paise Only	24465.00	Rupees Twenty Four Thousand Four Hundred Sixty Five Only
	Total Amount (Rs.)			One		311431.84	Rupees Three Lakh Eleven Thousand Four Hundred Thirty One and Eighty Four Paise Only

Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
BIDDERS QUOTING AREA							
				Departemental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	Notes : 1.The quotationer shall quote either plus or minus sign (eg: +5 or 5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail 5.Wrongful entry of quotes shall entail disqualifications besides other actions as the Employee deem fit.			311431.84			
" This is a Electronic Submission No Need of Signature"							