

# COCHIN PORT AUTHORITY

[www.tenderwizard.com/CPT](http://www.tenderwizard.com/CPT)

Tender No: T6/T-2003/2024-C Date: 05.04.2024- (PRICE BID)

**Name of Work: "RECTIFICATION TO THE SERVICE ROAD (NORTHERN SIDE) NEAR KALAMUKKU JUNCTION BY PROVIDING INTERLOCKING TILES (RETENDER)"**

## SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Please Enter the Contractor Name							
Sl.No:	Sub- heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains, not exceeding 30CM in depth but exceeding 1.50m in width as well as 10 Sqm. on plan, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m and lift upto 1.50 m. All kinds of soil including cost of all labour,tools, equipments etc. complete as per detailed specifications and directions of the Engineer-in-charge.	20.00	One Square Metre	125.78	<b>Rupees One Hundred Twenty Five and Seventy Eight Paise Only</b>	2515.60	<b>Rupees Two Thousand Five Hundred Fifteen and Sixty Paise Only</b>

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
2	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved dumping ground with a lead of 6 kms as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved including cost of all labour, tools, equipments etc. complete as per the direction of the Engineer-in-charge.	3.00	One Cubic Metre	188.70	<b>Rupees One Hundred Eighty Eight and Seventy Paise Only</b>	566.10	<b>Rupees Five Hundred Sixty Six and Ten Paise Only</b>
3	Providing, laying, spreading and compacting graded stone aggregate(size range 53 mm to 0.075 mm ) to wet mix macadam (WMM) specification including premixing the material with water at OMC in mechanical mix plant for all leads & lifts, laying in uniform layers with mechanical paverfinisher in subbase / base course on well prepared surface and compacting with vibratory roller of 8 to 10 tonne capacity to achieve the desired density, including cost of all labour, materials, equipments, tools etc. complete as per detailed specifications and	13.00	One cubic metre	3589.77	<b>Rupees Three Thousand Five Hundred Eighty Nine and Seventy Seven Paise Only</b>	46667.01	<b>Rupees Forty Six Thousand Six Hundred Sixty Seven and One Paise Only</b>

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
4	Providing and laying factory made 100mm thick Cement Concrete paver blocks of M40 grade, thickness & size/ shape, made by table vibratory method , to attain superior smooth finish using PU or equivalent moulds, laid in required colour & pattern over 50mm thick compacted bed of 6mm coarse aggregate, compacting and proper embedding / laying of inter locking paver blocks into the 6mm coarse aggregate bedding layer through vibratory compaction by using plate vibrator, filling the joints with crusher sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in drive ways or traffic parking including cost of all labour, materials, equipments etc. complete as per manufacturer's specifications/ detailed specifications & direction of Engineer -in-Charge.	510.00	One square metre	1030.00	<b>Rupees One Thousand Thirty Only</b>	525300.00	<b>Rupees Five Lakh Twenty Five Thousand Three Hundred Only</b>
	Total					575048.71	

Sl.No:	Sub-heads and items of work	Approximate Quantity	Unit	Departmental rates (Rs) in figures	Departmental rates (Rs) in words	Amount (Rs) in figures	Amount (Rs) in words
<b>BIDDER'S QUOTING AREA</b>							
				Departmental Estimated amount	Percentage quoted above/ below the Departmental Amount		Above/ Below
Percentage quoted above/ below the departmental amount shown in the above schedule					In Figures	In Words	
	<b>Notes :</b> 1.The quotationer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words 2. Only two decimal digits shall be accepted 3.quotationers shall also quote Above/ Below in words themselves in the last column. 4.In case of discepancy in words and figures the quoted figure in word will prevail			575048.71			
<b>" This is a Electronic Submission No Need of Signature"</b>							