COCHIN PORT AUTHORITY

GOVT. OF INDIA

BOQ - 3 PANEL RMU & CMU

SUPPLY

SL NO.	ITEM DESCRIPTION	QTY	UOM	RATE	AMOUNT
1	Supply of 3 Panel SF6 RMU 11kV, 630A, 21kA, Motoroperated, Compact, Outdoor, both side Extensible,Non drawout type, +CCV+ with SCADA Compatible FRTU (2nos. Load Break Switch (OD) incomer and 1no. fixed type motor operated Vacuum Circuit Breaker (VL)outgoing), all live parts enclosed in a robotically welded stainless steel tank of IP 67 class of protection. With Battery,Battery Charger,2Nos FPI, Auxilliary PT & with SF6 Gas density Manometer & Duplex Painting.	2	NOS		
2	Supply of Commercial Metering Unit with Space Heaters, TTB, AL Busbars etc..(without CT & PT) (Provision for installing 3 phase HT CT Energy meter)	1	NO.		
	TOTAL AMOUNT				

INSTALLATION

SL NO.	ITEM DESCRIPTION	QTY	UOM	RATE	AMOUNT
3	Installation, Testing and Commissioningof 3 Panel SF6 RMU 11kV, 630A, 21kA, Motoroperated, Compact, Outdoor, both side Extensible,Non drawout type, +CCV+ with SCADA Compatible FRTU (2nos. Load Break Switch (OD) incomer and 1no. fixed type motor operated Vacuum Circuit Breaker (VL)outgoing), all live parts enclosed in a robotically welded stainless steel tank of IP 67 class of protection. With Battery,Battery Charger,2Nos FPI, Auxilliary PT & with SF6 Gas density Manometer & Duplex Painting.	2	NOS		
4	Installation, Testing and Commissioning of Commercial Metering Unit with Space Heaters, TTB, AL Busbars etc..(without CT & PT) (Provision for installing 3 phase HT CT Energy meter)	1	NO.		
5	Providing suitable RCC Foundation for the 3 Panel RMU	2	NOS		
6	Providing suitable RCC Foundation for the CMU	1	NO.		
	TOTAL AMOUNT				