COCHIN PORT AUTHORITY

www.tenderwizard.com/CPT

Tender No: T6/T-2077/2026-C Dated: 13/01/2026 (PRICE BID)

Name of Work: "RESURFACING THE ROAD JN.LEADING TO AMBEDKAR STATUE WITH PAVER BLOCK AT WILLINGDON ISLAND".

SCHEDULE- A- SCHEDULE OF QUANTITIES TO BE DONE ON CONTRACT

Name and Address of the Vendor							
Sl. No:	**Sub- heads and items of work**	**Approximate Quantity**	**Unit**	**Departmental rates (Rs) in figures**	**Departmental rates (Rs) in words**	**Departmental Amount (Rs) in figures**	**Departmental Amount (Rs) in words**
1	Clearing the dust, earth, rubbish etc accumulated in the side of the road , wharf frontage/berths, container yard etc including sweeping and depositing the materials upto a lead of 6 Km as per the direction of Engineer-in-charge	**100**	m^2	**₹ 13.20**	Rupees Thirteen and Twenty Paise Only	**₹ 1,320.00**	Rupees One Thousand Three Hundred Twenty Only
2	Providing, laying, spreading and compacting graded stone aggregate(size range 53 mm to 0.075 mm) to Wet Mix Macadam (WMM) specification including premixing the material with water at OMC in mechanical mix plant, carriage of mixed material by tipper to site, for all leads&lifts, laying in uniform layers with mechanical paver finisher in sub-base/base course on well prepared surface and compacting with vibratory roller of 8-10 tonne capacity to achieve the desired density, complete as per specification and directions of Engineer -in- charge.	**62**	m^3	**₹ 3,244.23**	Rupees Three Thousand Two Hundred Forty Four and Twenty Three Paise Only	**₹ 2,01,142.26**	Rupees Two Lakh One Thousand One Hundred Forty Two and Twenty Six Paise Only
3	Providing and laying factory made 100 mm thick Cement Concrete paver blocks (M-40 grade) thickness & size, made by table vibratory method, to attain superior smooth finish using PU or equivalent moulds, laid in required colour & pattern over 50 mm thick compacted bed of 6 mm coarse aggregate, compacting and proper embedding/ laying of inter locking paver blocks into the 6 mm coarse aggregate bedding layer through vibratory compaction by using plate vibrator, filling the joints with crusher sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand in drive ways or light traffic parking etc. all complete as per manufacturer's specifications & direction of Engineer-in-charge	**500**	m^2	**₹ 1,280.00**	Rupees One Thousand Two Hundred Eighty Only	**₹ 6,40,000.00**	Rupees Six Lakh Forty Thousand Only
4	Random rubble masonry with hard stone in foundation and plinth including levelling up with cement concrete 1:6:12 (1 cement : 6 coarse sand : 12 graded stone aggregate 20 mm nominal size) upto plinth level with :Cement mortar 1:6 (1 cement : 6 coarse sand), all complete as per directions of Engineer-in charge	**5**	m^3	**₹ 8,138.96**	Rupees Eight Thousand One Hundred Thirty Eight and Ninety Six Paise Only	**₹ 40,694.80**	Rupees Forty Thousand Six Hundred Ninety Four and Eighty Paise Only
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources) (For pre-cast cover slab work).	**2.5**	m^3	**₹ 10,069.82**	Rupees Ten Thousand Sixty Nine and Eighty Two Paise Only	**₹ 25,174.55**	Rupees Twenty Five Thousand One Hundred Seventy Four and Fifty Five Paise Only
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.Hot rolled deformed bars incl all materials,labour,sundries, binding wire etc	**250**	Kg	**₹ 120.06**	Rupees One Hundred Twenty and Six Paise Only	**₹ 30,015.00**	Rupees Thirty Thousand Fifteen Only

7	Manufacturing, supplying and fixing retro reflective sign boards made up of 2 mm thick aluminium sheet, face to be fully covered with high intensity encapsulated type heat activated retro reflective sheeting conforming to type - IV of ASTM-D 4956-01 in blue and silver white or other colour combination including subject matter, message (bi-lingual), symbols and borders etc. as per IRC ; 67:2001, pasted on substrate by an adhesive backing which shall be activated by applying heat and pressure conforming to class -2 of ASTM-D-4956-01 and fixing the same with suitable sized aluminium alloy rivets @ 20 cm c/c to back support frame of M.S. angle iron of size 25x25x3 mm along with theft resistant measures, mounted and fixed with 2 Nos. M.S. angles of size 35x35x5 mm to a vertical post made up to M.S. Tee section ISMT 50x50x6 mm welded with base plate of size 100x100x5 mm at the bottom end and including making holes in pipes, angles flats, providing & fixing M.S. message plate of required size, steel work to be painted with two or more coats of synthetic enamel paint of required shade and of approved brand & manufacture over priming coat of zinc chromate yellow primer (vertical MS-Tee support to be painted in black and white colours).Backside of aluminium sheet to be painted with two or more coats of epoxy paint over and including appropriate priming coat including all leads and lifts etc. complete as per drawing , specification and direction of Engineer-in-charge.Mandatory/ Regulatory sign boards of 900 mm diametre with support length of 3750 mm	**3**	Nos	**₹ 7,996.58**	Rupees Seven Thousand Nine Hundred Ninety Six and Fifty Eight Paise Only	**₹ 23,989.74**	Rupees Twenty Three Thousand Nine Hundred Eighty Nine and Seventy Four Paise Only
	GRAND TOTAL					**₹ 9,62,336.35**	Rupees Nine Lakh Sixty Two Thousand Three Hundred Thirty Six and Thirty Five Paise Only

BIDDERS QUOTING AREA

		Departemental Estimated amount	**Percentage quoted above/ below the Departmental Amount**		**Above/ Below**
	Percentage quoted above/ below the departmental amount shown in the above schedule		**In Figures**	**In Words**	
	Notes : **1. The Tenderer shall quote either plus or minus sign (eg: +5 or -5) and in figures and words** **2. Only two decimal digits shall be accepted** **3. Tenderers shall also quote Above/ Below in words themselves in the last column.** **4.In case of discepancy in words and figures the quoted figure in word will prevail**	**₹ 9,62,336.35**			

" This is an Electronic Submission. No Need of Signature"